

Aggregate Optimization Chart

MIX ID'S: DDD0K7E7 and DDD0K7E9

Production Gradation Report

PLANT #: **P-103**

Sample Date: 3/20/17

Concrete Grade: DM

Contractor: _____

Dates Test Represents: 3/20/2017 to 3/26/2017

MDOT No.: _____

Agg. Class	Pit #	Source	Weight (SSD)	ft ³	Specific Gravity	% Contribution
6AA	58-003	Stoneco	1400	8.34	2.69	46.8
26A	58-003	Stoneco	370	2.20	2.69	12.4
2NS	81-93	Burmeister	1220	7.41	2.64	40.8
Total Wt			2990	17.95		100.0

<----- Verify this number is 100%




Superior Materials, LLC
 30701 W. 10 Mile Rd.
 Suite 500
 Farmington Hills, MI 48336

Sieve	6AA	26A	2NS	Cumulative % Passing	% Retained	Cumulative % Retained
2"	100.0	100.0	100.0	100.0	0.0	0.0
1.5"	100.0	100.0	100.0	100.0	0.0	0.0
1"	100.0	100.0	100.0	100.0	0.0	0.0
3/4"	83.4	100.0	100.0	92.2	7.8	7.8
1/2"	41.6	99.5	100.0	72.6	19.6	27.4
3/8"	19.2	90.0	100.0	60.9	11.7	39.1
#4	2.2	14.7	99.5	43.4	17.5	56.6
#8	1.6	3.5	86.3	36.4	7.1	63.6
#16	1.7	1.7	69.8	29.5	6.9	70.5
#30	1.6	1.3	48.7	20.8	8.7	79.2
#50	1.6	1.2	15.6	7.3	13.5	92.7
#100	1.6	1.2	2.9	2.1	5.2	97.9
LBW	1.2	1.0	1.2	1.2	0.9	98.8

*Maximum % Retained must be above the 3/8" sieve.
 *Any two adjacent sieves must equal 10% except max., nom. max., #100 and #200 sieves.
 *% Retained must be at least 4% for each sieve except max., nom. max., #100 and #200 sieves.
 *% Retained must be at least 8% for the 1" sieve when a 2" max. size (nom. Max. 1.5") aggregate is used.

Production Gradation Batch Plant Gradations Aggregate Supplier Gradations

Coarseness Factor: 61 **Workability Factor: 36**



Initial Production Sample (IPS)

Coarseness Factor: 61		Workability Factor: 36	
Sieve	Cumulative % Passing	% Retained	Cumulative % Retained
2"	100.0	0.0	0.0
1.5"	100.0	0.0	0.0
1"	99.3	0.7	0.7
3/4"	89.2	10.1	10.8
1/2"	70.7	18.5	29.3
3/8"	60.7	10.0	39.3
#4	44.4	16.3	55.6
#8	35.9	8.5	64.1
#16	27.3	8.6	72.7
#30	19.1	8.2	80.9
#50	7.4	11.7	92.6
#100	1.9	5.6	98.1
LBW	0.7	1.2	99.3

PREPARED BY:
 SM, LLC Technical Service

Approved BY:

Aggregate Optimization Chart

MIX ID'S: DDD0K7E7 and DDD0K7E9

Production Gradation Report

PLANT #: **P-38**

Sample Date: 3/20/17

Concrete Grade: DM

Contractor: _____

Dates Test Represents: 3/20/2017 to 3/26/2017

MDOT No.: _____

Agg. Class	Pit #	Source	Weight (SSD)	ft ³	Specific Gravity	% Contribution
6AA	58-003	Stoneco	1400	8.34	2.69	46.8
26A	58-003	Stoneco	370	2.20	2.69	12.4
2NS	81-93	Burmeister	1220	7.41	2.64	40.8
Total Wt			2990	17.95		100.0

<----- Verify this number is 100%

Sieve	6AA	26A	2NS	Cumulative % Passing	% Retained	Cumulative % Retained
2"	100.0	100.0	100.0	100.0	0.0	0.0
1.5"	100.0	100.0	100.0	100.0	0.0	0.0
1"	100.0	100.0	100.0	100.0	0.0	0.0
3/4"	83.4	100.0	100.0	92.2	7.8	7.8
1/2"	41.6	99.5	100.0	72.6	19.6	27.4
3/8"	19.2	90.0	100.0	60.9	11.7	39.1
#4	2.2	14.7	99.5	43.4	17.5	56.6
#8	1.6	3.5	86.3	36.4	7.1	63.6
#16	1.7	1.7	69.8	29.5	6.9	70.5
#30	1.6	1.3	48.7	20.8	8.7	79.2
#50	1.6	1.2	15.6	7.3	13.5	92.7
#100	1.6	1.2	2.9	2.1	5.2	97.9
LBW	1.2	1.0	1.2	1.2	0.9	98.8




Superior Materials, LLC
 30701 W. 10 Mile Rd.
 Suite 500
 Farmington Hills, MI 48336

*Maximum % Retained must be above the 3/8" sieve.
 *Any two adjacent sieves must equal 10% except max., nom. max., #100 and #200 sieves.
 *% Retained must be at least 4% for each sieve except max., nom. max., #100 and #200 sieves.
 *% Retained must be at least 8% for the 1" sieve when a 2" max. size (nom. Max. 1.5") aggregate is used.

Production Gradation Batch Plant Gradations Aggregate Supplier Gradations

Coarseness Factor: 61 **Workability Factor: 36**



Initial Production Sample (IPS)

Sieve	Cumulative % Passing	% Retained	Cumulative % Retained
2"	100.0	0.0	0.0
1.5"	100.0	0.0	0.0
1"	99.3	0.7	0.7
3/4"	89.1	10.2	10.9
1/2"	70.5	18.6	29.5
3/8"	60.5	10.0	39.5
#4	44.1	16.4	55.9
#8	35.6	8.5	64.4
#16	27.7	7.9	72.3
#30	20.6	7.1	79.4
#50	8.7	11.8	91.3
#100	1.6	7.1	98.4
LBW	1.1	0.6	98.9

PREPARED BY:
 SM, LLC Technical Service

Approved By: